



HRBT Expansion Project

Tunnel Talk

topic	Tunnel Boring Operation – Slurry Walls
presenter	Raphael Delhayé HRCP Deputy Project Manager-Tunnel Approaches
date	Thursday, January 28, 2021
time	12:00 to 1:30 PM
place	Virtual Meeting Platform via Microsoft Teams
audience	ASHE Members

Slurry Wall Talk


January 28, 2021
Raphaël Delhayé

Introduction



Table of Contents:

1. Definitions
2. DWALL installation
3. Guide walls
4. Excavations
5. Slurry fluid management
6. Reinforcement fabrication
7. Concrete placement
8. Quality control





Why do we have slurry walls on the project ?

Why do we have slurry walls on the project?



What ?

A wall built using trenches excavation techniques under slurry fluid management

Why ?

Support of Excavations (SOE) for Tunnel Approach Structures South & North Island

- Launching pit
- Bore Proximity Walls
- Approaches

How ?


With a very specific technique involving giant excavating tools, cranes, etc.

Who ?


HRCP/KELLER North America

When ?

August 2020 – June 2022



Why do we have slurry walls on the project?



Why do we have slurry walls on the project?



Why do we have slurry walls on the project?



A total of :

25 millions lbs of steel

128,300cy of concrete

16,000 trucks hauling spoils

22 Months of activity




Diaphragm Wall: Definitions and Uses

Part 1

TUNNEL APPROACH STRUCTURE

“Slurry Wall”

A term widely used to describe the construction of a **concrete wall** using slurry fluid to support the excavated trench before replacing it by tremie concrete



“Diaphragm Wall”

A diaphragm wall is a reinforced concrete wall excavated under a slurry fluid using the panel method.



“Slurry Cutoff Wall” or “Slurry Trenches”

Describes a wall excavated under slurry to install water cutoff barrier or environmental barrier.



Diaphragm wall Advantages:

- Either a temporary or permanent structure
- Great stiffness
- This is a very important consideration when working in an urban environment.
- In addition to its retaining role, a diaphragm wall can have other functions:
 - Load bearing foundations - Barrettes
 - Hydraulic cut-off




Diaphragm Wall Installation

Part 2

TUNNEL APPROACH STRUCTURE

2. Diaphragm wall schematic



2. Diaphragm wall schematic

1 – Guide walls



2 – Panel excavation



2. Diaphragm wall schematic

3 – Rebar cage placement



4 – Cast concrete under slurry





Guide Walls

Part 3

TUNNEL APPROACH STRUCTURE


3. Guide Walls

Guide Walls:

Temporary structure constructed in advance and consisting of two reinforced concrete sections.

Functions:

- Confirms the location of the wall (layout)
- Guide the excavation tool and ensure verticality
- Support for suspension of reinforcement cages





Excavations

Part 4

TUNNEL APPROACH STRUCTURE

4. Excavations

Excavating Tools:



Hydraulic Clamshell Bucket

- Equipped with real time monitoring device
- Great productivity, monitoring and correction of the verticality if necessary.

Currently, HRCP/Keller has one clamshell working on the South Island.



4. Excavations

Excavating Tools:



Hydrofraise

- A Hydrofraise consists of two counter-rotating drums on horizontal axes fitted with cutting teeth.
- Continuous excavation under engineered slurry
- Cut soil and rock into particles which are pumped to the desanding plant
- Particles from slurry will be separated and cleaned slurry is returned to excavation location
- Excavation progress verticality is monitored in real time





2 hydrofraises are currently working for HRCF
We call them: the Queen and the King

4. Excavations

Paneling Method



Primaries and Secondaries




4. Excavations

Excavation



Diaphragm wall installation



Water plant : 15 tanks

Slurry plant : 43 tanks

Current work zone

- 2 hydromills
- 1 clamshell
- 4 cranes

**Cages fabrication
area**

**100% of the island surface
is mobilized to achieve
the Dwall activities.**



Slurry Fluid Management

Part 5

TUNNEL APPROACH STRUCTURE



What do you know about Mud drilling ?

Slurry Treatment plant

Main function

Maintain borehole / panel stability

- Prevent collapses
- Prevent water inlets into excavation
- Remove cuttings for reverse circulation technique
- Lubricate drilling tool



Slurry Treatment plant

- Slurry: water and bentonite powder mixed with high shear mixer.
- The development of a thin impervious filter cake on the panel sidewalls controls the transfer of slurry in the soil and maintains the positive hydrostatic head.
- Relatively coarse and heavy particles are suspended in the viscous slurry.
- Sufficient viscosity and gel strength are important to transport the excavated material to the desanding plant (Hydromill operation)
- Prior to concrete placement, slurry will be desanded and cleaned




**43 tanks are on South
Island for bentonite slurry**

5. Slurry Fluid Management

5. Slurry Fluid Management

Slurry Treatment plant



Hydrofraise schematic of working principles

5. Slurry Fluid Management

5. Slurry Fluid Management



Slurry Treatment plant



5. Slurry Fluid Management

5. Slurry Fluid Management



Slurry Treatment plant



5. Slurry Fluid Management

5. Slurry Fluid Management



Type of Contamination



Cement



Creeping clay



Reinforcement Fabrication


Part 6

TUNNEL APPROACH STRUCTURE


Reinforcement and buildability considerations

A diaphragm wall reinforcement cage includes the following:

- Structural bars:
 - main vertical bars to resist bending moments,
 - horizontal bars to resist shear force.
- Block-outs for ground anchors, slab, etc.
- Bars required for installation such as lifting bars





- **2 cages** per panel
- Total weight of **120,000lbs**
- **800 CY** of concrete



Y panels: 4 major critical points on the slurry walls construction

- **3 cages** per panel
- Total weight of **400,000lbs**
- One special crane (750t) to install the cages
- **1,200cy** of concrete



- Reinforcement cages are built horizontally on the ground
- Shear keys / blockouts are installed inside the cages
- Reinforcement is typically made of two 90-ft cages
- Cage will be suspended and anchored on top of the guide-walls





Concrete Placement



Part 7

TUNNEL APPROACH STRUCTURE

- Tremie pipes are assembled and lowered and placed in designated location
- Concrete is placed from the bottom to the top
- The slurry displaced is pumped back to the treatment plant.



7. Concrete Placement





Quality Control

Part 8

TUNNEL APPROACH STRUCTURE

Phases of controls

During excavation

- Test of trench geometry
- Slurry parameters

During cage fabrication

- Steel conformity
- Compliance with shop drawings

During concreting the panel


- Test of concrete
- Record of concrete curve placement

After panel completion

- Test of panel integrity
- Test of concrete strenght


Quality Control Steps

- Example of Hydromill on-board Instrumentation to ensure verticality control



Quality Control Steps

- Example of using immersed sonar to ensure excavation verticality during and after excavation
- HF: 0.75%
- KS:1%





8. Quality control

8.2 Integrity testing



Thermal & Sonic Analysis

- Confirm panel integrity
- Anticipate defects and repairs





8. Quality control

8.3 Reinforcement testing



Quality control of rebar cages

- Confirm all the reinforcement is properly installed prior to lifting the cage
- Insure concrete coverage



WHAT MUD TESTS DO YOU KNOW?

- **Viscosity**

- Stability of the excavation
- Spoil in suspension *one question !!*

- **Density**

- Verification of slurry dosage
- Measurement of the mud's physical load

- **Filtrate/filter cake**


- Waterproofing of the wall
- Water retention capacity of the mud

- **pH**

- Normally pH 7 (natural sodium) to 9 (activated)
- Influence of the ground pH => interferes with mud performance

- **Sand content**

- Physical load of the mud which can be only treated mechanically
- Sand and/or silt remover ($> 74\mu\text{m}$)



SPECS 31 56 00 : CHARACTERISTICS OF THE MUD

Measure	Fresh mud	Working mud	Before concreting
Marsh Viscosity (s)	> 36s	> 32s	> 32s
Density	65 pcf min 1.04	65 – 80 pcf 1.04 – 1.28	65 - 72 pcf 1.04 - 1.15
Filtrate (ml)	20ml in 30 min	< 30 mL	< 30mL
pH	N/A	7 - 12	7-12
Sand content (%)	N/A	< 5	< 4

7. Concrete Placement

8.4 Concrete




- Every truck is tested prior to being allowed to pour
- Objective is to confirm the strength of the whole structure






1. Slump flow: Each truck
2. Unit weight: Each batch or truck until a minimum of three consecutive batches meet the requirements and every 50 cy daily.
3. Temperature: Each batch or truck until a minimum of three consecutive batches meet the requirements and every 50 cy daily
4. Compressive strength: 7 cylinders / day or 150 cu yards. Out of 5 cylinders, 3 tested at specified age, 2 at 7 days and 2 at 28 days.
5. Durability tests: start every 200 cy for first, 2000 cy and every 500 cy thereafter.
6. Monitoring: Monitor placement and chart actual volume of concrete placed versus theoretical volume required.

1. Crosshole Sonic Logging (CSL) Testing is a slurry wall integrity test to detect concrete deficiencies.
2. Probes are inserted into vertical access tubes cast into the panels during construction.
3. 60200 LF CSL tubes (430 EA)
4. The 2 inch CSL tube will be steel pipe schedule 40. The 2 inch CSL tube will be PVC on the TBM breakthrough.
5. The CST Test is performed between 72 hours and 25 calendar days after concrete placement, and after the concrete f'_c exceeds 3000 psi.
6. Concrete quality ratings from CSL Testing:




TYPICAL 3-BITE PRIMARY PANEL CSL LAYOUT
Scale: 1/4" = 1'-0"



TYPICAL 1-BITE PRIMARY PANEL CSL LAYOUT
Scale: 1/4" = 1'-0"

Table 31 56 00-4: Concrete Quality Ratings from CSL Testing

Category	First Pulse Arrival Time (FAT) Increase	AND / OR	Signal Reduction	Comment
G	Up to 10%	AND	< 6 db	Good
Q	10 to 20%	AND	< 9 db	Questionable
P/F	21 to 30%	OR	9 to 12 db	Poor/Flaw
P/D	> 30 %	OR	> 12 db	Poor/Defect



TYPICAL CLOSING PANEL CSL LAYOUT
Scale: 1/4" = 1'-0"

8. Quality control



8.5 Thermal Testing:



Thermal Testing:

1. 1125 thermocouples EA
2. 3 pairs of thermocouples shall be placed at a minimum depth of 10 feet from top of panel
3. Max concrete temperature: 170 deg F
4. Record the temperature at each thermocouple at least once every hour for at least 2 hours prior to the anticipated start of placement until 3 days. Temperatures shall be reviewed by the tunnel QC manager every 12 hours to verify compliance with temperature limits.
5. Avoid shrinkage and thermal cracking

LEGEND
S1, S2 AND S3 ARE PLACED IN THE MIDDLE OF THE WALL 10' BELOW TOP OF THE WALL.
IN SECTION VIEW, S2 AND S3 ARE PLACED IN THE SAME HORIZONTAL PLANE AS S1 AND ATTACHED TO THE REINFORCING STEEL 5" TO THE OUTER FACE OF THE WALL.





THANK YOU
FOR YOUR ATTENTION